PARKHILLSMITH&COOPER

ADDENDUM NO: 4

TO: ALL PLANHOLDERS

FROM: PARKHILL, SMITH & COOPER, INC. 12/12/11

PROJECT NAME: Sterling City ISD Ag Facility and Concession Building

PROJECT NO.: 03.9145.11

DATE: 12/12/11

Attention of all Prospective Bidders/Plan Holders is directed to the following modifications to the referenced Plans and Specifications. This Addendum forms a part of, and shall be attached to the Contract Documents, and modifies the original Bidding Documents dated November 2011 as noted below:

This Addendum consists of 1 page

I. CLARIFICATION

A. Roof panels for the Ag Facility are to be galvalume.
B. The door to be installed in aluminum frame AL-02 is aluminum entry as specified.
C. Refer to A4/L-100, keyed note 6 - this is to indicate that the turf in this area is to pulled back from the location that the CMU fence is to be constructed, protected and reinstalled. It is not to require that the turf should be removed stored and reinstalled over the entire play area.
D. Projection screens will not be required on this project. Include electrical requirements as per sheet E-103, keyed note 14.
E. In the event the bridge crane is not accepted, the structural shall not be downgraded to accommodate the future installation of the crane.
F. Refer to the project manual, Specification Section 16726 - this work is to be included in this project
G. On the proposal form, indicate addendum of the project 03 9146 that were issued prior to it being included in project 039145 with an “e” suffix. As an example, the format will be “Addendum No 1e.” The addendum for project no. 03 9145 will be listed as published.
H. Include painting the structural steel members of the bridge in this project.

II. CHANGES TO PROJECT MANUAL: NONE

III. CHANGES TO DRAWINGS: NONE

END OF ADDENDUM NO. 4

Amarillo
El Paso
Las Cruces
Lubbock
Midland

1700 W. Wall Street Suite 100 Midland, Texas 79701 432.697.1447 Fax 432.697.9758